

From:

[Norm Electrical Engineering](#)

23 Park View Road

N17 9AT

Tottenham, London

United Kingdom

Tel: 020 8245 8400

Mob: 07724 308998

Email: info@normelectric.co.uk

NAPIT Registered Contractor

ECS Gold Card Electrician

Invoice Number	INV-2576
Invoice Date	03/11/2025
Total Due	£325.00

To:

Hasan

177a Leytonstone Road Stratford E15 1LH

+44 7764 331605

hasan_gha1@hotmail.com

EICR Remedial work (Domestic Electrical Installation Condition Report-29-10-2025-E151LH (2025102950))

Hrs/Qty	Service	Rate/Price	Adjust	Sub Total
1	Electrical Services and Materials Supply Upgrade existing consumer unit protection by replacing wrong RCBO with individual RCBOs (Residual Current Breaker with Overcurrent Protection) in accordance with BS 7671:2018 (18th Edition) Wiring Regulations.	£85.00	0.00%	£85.00

Thanks for choosing [Norm Electrical Engineering](#) | info@normelectric.co.uk Thanks for choosing Norm Electrical Engineering Hope to work on next projects .

Hrs/Qty	Service	Rate/Price	Adjust	Sub Total
1	Electrical Services and Materials Supply The pull cord switch was found hanging from the ceiling, unsafely supported only by its electrical cables. This presented a high risk of electric shock and circuit damage.	£40.00	0.00%	£40.00
1	Electrical Services and Materials Supply Main Protective Bonding - Gas Pipework Installation of main protective bonding conductor from the main earthing terminal (MET) to the gas meter pipe, using 10mm ² green/yellow cable and BS 951 bonding clamps. The bonding cable will be installed surface-mounted and visible along its route (in uPVC White Mini Trunking) up to the door inside the property. After the door, the cable will not be in trunking, as the floor and corners are not suitable for trunking installation. However, we will try our best to achieve the neatest possible finish. All connections will be securely terminated, labelled, and tested to verify continuity and compliance with BS 7671:2018 (18th Edition) Wiring Regulations. and uPVC White Mini Trunking Purpose: To ensure safe and compliant equipotential bonding between electrical and gas installations.	£200.00	0.00%	£200.00
1	Electrical Installation Condition Report (EICR) Completion of minor electrical works as identified in EICR Ref: [2025102950]. Re-testing of affected circuits and issuance of satisfactory Electrical Installation Condition Report (EICR).	£0.00	0.00%	£0.00

Sub Total	£325.00
-----------	---------

Thanks for choosing [Norm Electrical Engineering](https://normelectric.co.uk) | info@normelectric.co.uk Thanks for choosing
Norm Electrical Engineering Hope to work on next projects .



Invoice

Tax	£0.00
Total Due	£325.00

Norm Electrical Engineering
Bank :Lloyds
Sort Code : 30-99-50
Account Number :89187160

Payment is due within 30 days from date of invoice. Late payment is subject to fees of 5% per month.[Terms & Conditions](#)