



Quote

From:

[Norm Electrical Engineering](#)

23 Park View Road

N17 9AT

Tottenham/Haringey

London

02082458400

07724308998

info@normelectric.co.uk

Quote Number	2593
Quote Date	17/07/2026
Valid Until	01/08/2026
Total	£645.80

To:

Jake Morris

N4 3LQ, number 46a.

jakemor@gmail.com

This quotation covers the recommended remedial works identified during the **Domestic Electrical Installation Condition Report (EICR)** carried out on **15/07/2026**. The proposed works are intended to rectify the observations recorded within the report and improve the safety and compliance of the electrical installation with the current edition of **BS 7671**. Upon completion of the agreed remedial works, the relevant certification will be issued where applicable.

Thanks for choosing [Norm Electrical Engineering](#) | info@normelectric.co.uk Hope to work together on this projects .

Hrs/Qty	Service	Rate/Price	Adjust	Sub Total
1	Install Main Protective Gas Bonding Conductor Supply and install a 10 mm ² main protective bonding conductor from the main earthing terminal (MET) to the gas meter installation pipework, including suitable cable clips, earth clamp, identification label, testing, and verification in accordance with the current edition of BS 7671. Labour only. Please note: As the main protective bonding conductor may need to be installed through a communal area, permission from the management or the owner of No. 46 may be required before the works can proceed. Any permissions required are the responsibility of the client to obtain prior to the commencement of works.	£275.00	0%	£275.00
1	Materials – Main Protective Gas Bonding Installation Supply of materials for the installation of a 10 mm ² main protective bonding conductor from the main earthing terminal (MET) to the gas meter installation pipework, including 10 mm ² green/yellow bonding cable, BS 951 earth clamp, cable clips/fixings, warning labels, and all associated consumables required for a compliant installation in accordance with the current edition of BS 7671.	£26.00	0%	£26.00

Hrs/Qty	Service	Rate/Price	Adjust	Sub Total
1	Other Remedial Works – Labour Carry out minor remedial works identified during the EICR, including the installation or replacement of junction boxes where required, enclosure of exposed conductors, cable terminations, minor wiring alterations, accessory repairs or replacements, testing, verification, and commissioning. All works will be carried out in accordance with the current edition of BS 7671.	£120.00	0%	£120.00
1	Materials – Junction Boxes & Electrical Accessories Supply of materials required for the remedial works, including maintenance-free junction boxes, IP-rated (waterproof) junction boxes where required, WAGO connectors, cable clips, fixings, insulating materials, and all associated consumables necessary to complete the installation in accordance with the current edition of BS 7671.	£22.00	0%	£22.00
1	Replace Type AC RCD with Type A RCD Isolate the electrical installation, remove the existing Type AC RCD, and install a new Type A RCD. Carry out testing, verification, and recommissioning of the installation to confirm correct operation and compliance with the current edition of BS 7671.	£70.00	0%	£70.00
1	Materials Type A RCD Supply of Type A RCD compatible with the existing consumer unit, together with any required fixings, identification labels, and associated consumables necessary for installation in accordance with the current edition of BS 7671.	£67.80	0%	£67.80

Thanks for choosing [Norm Electrical Engineering](http://normelectric.co.uk) | info@normelectric.co.uk Hope to work together on this projects .

Hrs/Qty	Service	Rate/Price	Adjust	Sub Total
1	Re-Issue Electrical Installation Condition Report (EICR) Following the satisfactory completion of the agreed remedial works, the Electrical Installation Condition Report (EICR) will be reviewed and re-issued to reflect the updated condition of the installation. Where applicable, the report outcome will be amended based on the completed remedial works and verification testing.	£65.00	0%	£65.00
1	Parking The client is responsible for providing a valid parking permit or suitable parking arrangements for the duration of the works. If no permit is provided and a Parking Charge Notice (PCN) is issued as a result of carrying out the works, the full cost of the PCN (currently £65 or £130, depending on the contravention) will be added to the final invoice and shall be payable by the client.	£0.00	0.00%	£0.00

Sub Total	£645.80
Tax	£0.00
Total	£645.80

This is a fixed price quote. If accepted, we require a 50% deposit upfront before work commences. If there is no other agreements. [Terms & Conditions](#)

Thanks for choosing [Norm Electrical Engineering](#) | info@normelectric.co.uk Hope to work together on this projects .